



NOTES:

1. Concrete 4,000 PSI at 28 days, minimum.
2. Steps are M.A. Industries #PS1-PF on 16" centers.
3. Grade adjustment rings available if required.
4. Sump Pits available where required (in place of gravity drain).



7415 Diley Road
Canal Winchester, OH 43110

Phone (614) 837-8444
Fax (614) 837-1198

2" Water Meter Pit
City of Columbus

Drawn by: TAK

Scale: n/a

Date: 10/28/04